SECTION 1: INVITATION TO TENDER & PROJECT BACKGROUND

1.1 Project Purpose: Oman Integrated Industrial & Port Zones SAOC (Duqm & Sohar) invites qualified environmental contractors to submit a comprehensive Technical and Commercial Proposal for integrated waste collection, recycling segregation, and hazardous waste haulage across Sohar Industrial Zone and Duqm Logistics Hub.

1.2 Contract Duration: The initial contract duration shall be 24 months commencing 1 December 2026.
1.3 Submission Deadline: All proposals must be submitted before 15 November 2026 at 14:00 GST.
1.4 Payment Terms: Standard payment credit period shall be 30 days from verified monthly invoice submission.

5.4 Special Contractual Clauses & Cross-Check Items (Page 2):
• Note on Contract Duration: The contract term is stated here as 12 months renewable option (Note: compare with Section 1.2 which states 24 months).
• Note on Payment Terms: Invoices shall be settled within 60 days net (Note: compare with Section 1.4 which states 30 days).
• Liquidated Damages / SLA Penalty: Delayed skip replacement beyond 24 hours attracts a penalty of 50 OMR per incident.
• Unconfirmed Item: Exact hazardous waste bay coordinates in Sector 7 are TBD subject to site survey.

SECTION 5: FLEET GPS TRACKING, WEIGHBRIDGE & BEAH MANIFEST COMPLIANCE

3.1 Mandatory Container & Fleet Scope of Work:
• General Waste Collection: 12 x 1,100 L galvanized bins collected 3x weekly across Zone A & Zone B warehouses.
• Segregated Cardboard & Recyclables: 6 x 1,100 L recycling bins collected weekly with monthly ISO 14001 diversion certificates.
• Industrial Skip Containers: 4 x 6 m3 chain-lift skips with 8 skip lifts per month.
• Bulk RoRo Containers: 3 x 30 CBM RoRo containers for industrial scrap and C&D debris with 6 RoRo trips per month.
• Hazardous Sludge & Chemical Drums: 15 Metric Tons per month of ADR-certified hazardous waste transport and manifested disposal.

SECTION 7: COMMERCIAL TERMS, SCHEDULE OF RATES & BILL OF QUANTITIES

Clause 7.4 — Operational & Technical Provisions (Page 4):
The Contractor shall maintain all waste containment equipment in serviceable, leak-proof, and sanitized condition at all times. All collection vehicles operating within Oman Integrated Industrial & Port Zones SAOC (Duqm & Sohar) premises must be equipped with real-time GPS telemetry, reverse alarms, spark arrestors, and spill containment kits.

Table 4.1 — Sub-Zone Operational Schedule (Page 4):
Zone Sector-5 | 1,100 L Bins & 6 m3 Skips | Collection: 3x Weekly | SLA: 24 Hours | Manifest: Required

• Requirement 4-A: Contractor must submit calibrated weighbridge tickets for every trip completed on Page 4.
• Obligation 4-B: Zero tolerance for unmanifested disposal or mixed hazardous/non-hazardous loads.

SECTION 9: CONTRACT DURATION, TERMINATION & PERFORMANCE BOND

10.1 Mandatory Questions Requiring Bidder Response (Page 5):
Q1: Please confirm your valid Be'ah and Environment Authority License numbers and attach ISO 14001 / 45001 certificates.
Q2: Please provide an itemized unit rate and monthly total schedule in OMR for all 1,100 L bins, 6 m3 skips, 30 CBM RoRo containers, and hazardous waste tonnage.
Q3: Please confirm your guaranteed emergency skip replacement SLA response time in hours.
Q4: Please clarify how cradle-to-grave 5-part Environment Authority waste manifests will be delivered each month.