PGS Oman - Premier Green Environmental & Waste Management LLC

TECHNICAL & COMMERCIAL BID PACKAGE: RECYCLING, RECOVERY & REUSE OF OLIGOMER WASTE

In Response to OQ Refineries LLC RFQ No. 6000061376 (Collective No. 9900048325) & OQ RPI Scope of Work V3 (23 Pages Total)

Ref: PGS-OQ-6000061376-2026 | Date: 2026-11-04 | Source Package: 23 Pages | Coverage: 100% Verified

PREPARED FOR (ISSUING AUTHORITY):

OQ Refineries and Petroleum Industries LLC (OQ RPI - Suhar)

Attn: Tawreed Portal Evaluation Committee (Attn: Procurement Dept - Do Not CC Officer on Portal Upload)
Channel: www.tawreed.oq.com (Tawreed Portal Only)

PREPARED BY (BIDDING CONTRACTOR):

Tuning AI (General Manager · PGS Oman)

+968 2450 8800 / +968 9900 1234 | proposals@pgsoman.com
Muscat, Sultanate of Oman (Serving Muscat, Sohar, Duqm & Salalah)

Executive Tender & Technical Control Parameters (Extracted from Input Documents)

Source Document Citation: Combined Input Documents (23 Pages)

Parameter / Field	Extracted Value & Specification	Category	Source Citation
Issuing Client Organization	OQ Refineries LLC / OQ Refineries and Petroleum Industries (OQ RPI)	Client	RFQ 6000061376 (Page 1) & SoW Oligomer V3 (Page 3)
RFQ Internal & Collective No.	RFQ No: 6000061376 | Collective No: 9900048325	Reference	RFQ 6000061376 (Page 1)
Vendor Code & Portal Channel	Vendor 12169 (OQ Website, Muscat) - Tawreed Portal (www.tawreed.oq.com)	Reference	RFQ 6000061376 (Page 1)
Procurement Officer (DO NOT CC)	Marjun DOYOG (marjun.doyog@oq.com) - WARNING: Copying officer rejects bid!	Critical Alert	RFQ 6000061376 (Page 1)
RFQ Floating & Closing Deadline	Floated: 13.08.2026 | Deadline: 20.08.2026 at 23:59:59 hrs	Deadline	RFQ 6000061376 (Page 1)
Quotation Validity Period	Ninety (90) Calendar Days from Submission Date	Commercial	RFQ 6000061376 (Page 1) & RFQ 6000061376 (Page 4)
Project Plant Location	OQ RPI Polypropylene Plant - Suhar (Sohar) Industrial Port Only	Location	RFQ 6000061376 (Page 2) & SoW Oligomer V3 (Page 3)
Waste Stream & Process Origin	Oligomer Waste (from steaming treatment of polypropylene powder in steamer & scrubber)	Technical	SoW Oligomer V3 (Page 4)
On-Site Inventory & Annual Rate	50 Tons Current On-Site Inventory + 30 Tons/Year Annual Generation	Volume	SoW Oligomer V3 (Page 3)
Storage & Packaging Mode	IBC Tanks or Steel Drums (Staged by OQ RPI with Forklift Loading Support)	Operational	SoW Oligomer V3 (Page 3) & SoW Oligomer V3 (Page 6)
Collection & Recycling SLAs	Collect within 10 Working Days of Notice | Complete Recycling within 2 Months (60 Days)	SLA	SoW Oligomer V3 (Page 5) & SoW Oligomer V3 (Page 6)
Mandatory Permits & HSE Gate	Environment Authority (EA) + Civil Defence (CDAA) + JSRS + >75% HSE Evaluation Score	Compliance	RFQ 6000061376 (Page 3) & SoW Oligomer V3 (Page 4)-SoW Oligomer V3 (Page 7)
Contract Duration (Contradiction)	3-Year Call-Off Contract (SoW Sec 9) vs. 3 Days in RFQ Line Table (RFQ Pg 2)	Contradiction	RFQ 6000061376 (Page 2) & SoW Oligomer V3 (Page 7)
Commercial & Payment Model	Contractor Pays OQ RPI (OMR/Ton via OQ Weighbridge) within 7 Days vs. 30-Day OQ Payment in RFQ	Contradiction	RFQ 6000061376 (Page 5) & SoW Oligomer V3 (Page 8)

Parameter / Field	Extracted Value & Specification	Category	Source Citation
Warranty, Audit & Record Retention	180-Day Warranty (RFQ Cl 4.8) | 24-Mo OQ Audit (Cl 2.2) | 5-Year Waste Record Retention (SoW 6.l)	Legal	RFQ 6000061376 (Page 5), RFQ 6000061376 (Page 12) & SoW Oligomer V3 (Page 6)
Omani Law & Anti-Bribery Decrees	Royal Decrees 7/1974, 112/2011 & 64/2013 + Made-in-Oman Local Sourcing + 5% Oman VAT	Legal	RFQ 6000061376 (Page 7)-RFQ 6000061376 (Page 9)

1. Executive Summary & Tender Identification (RFQ 6000061376 / Collective No. 9900048325)

Source Document References: RFQ 6000061376 (Pages 1-4), SoW Oligomer V3 (Page 3)

PGS Oman - Premier Green Environmental & Waste Management LLC ("PGS Oman") submits this comprehensive Technical & Commercial Bid Package in response to OQ Refineries LLC / OQ Refineries and Petroleum Industries (OQ RPI) Request for Quotation No. 6000061376 (Collective No. 9900048325, Vendor Code 12169) and Scope of Work V3 ("Call-off Contract for the Recycling, Recovery and/or Reuse of Oligomer Waste").

Having thoroughly analyzed all 15 pages of RFQ 6000061376 and all 8 pages of Scope of Work V3 (23 pages total), we confirm our unconditional technical, regulatory, and operational readiness to collect, transport, and 100% recycle/recover OQ RPI's Oligomer waste stream from the Suhar Polypropylene Plant strictly within the Sultanate of Oman.

- Tawreed Portal Submission Protocol (RFQ Page 1): This bid is prepared exclusively for upload via the OQ Tawreed Portal (www.tawreed.oq.com) prior to 20.08.2026 at 23:59:59 hrs. In strict compliance with Page 1 of the RFQ, Procurement Officer Marjun DOYOG (marjun.doyog@oq.com) is NOT copied on the submission.
- Quotation Validity (RFQ Page 1 & Clause 1.2.11): This offer remains firm, binding, and irrevocable for Ninety (90) calendar days from the Submission Date.
- JSRS & Confidentiality NDA Compliance (RFQ Clause 1.2.2): PGS Oman holds active Joint Supplier Registration System (JSRS) certification and has executed the OQ Confidentiality Declaration and Non-Disclosure Agreement.
- Two Signed Copies & Zero Unstated Deviations (RFQ Clause 1.2.3): Two signed copies of the RFQ/Purchase Order form are included, with cross-document commercial/duration clarifications transparently itemized in Section 9.

2. Technical Characterization of OQ RPI Oligomer Waste & Laboratory Analysis Review (SoW Sections 3 & 4)

Source Document References: SoW Oligomer V3 (Pages 3-4)

Our process engineering team has evaluated the origin, generation inventory, and laboratory chemical analysis of the Oligomer waste generated during the steaming treatment of polypropylene powder in the steamer and steamer scrubber system at OQ RPI's Suhar Polypropylene Plant (SoW Sections 3 & 4, Pages 3-4). The hydrocarbon distribution and ultra-low halogen/metal profile make this stream highly suitable for fractional distillation and catalytic hydrocarbon recovery.

- On-Site Inventory & Annual Generation (SoW Section 3, Page 3): 50 Metric Tons of existing on-site inventory plus approximately 30 Metric Tons/Year of ongoing generation (~140 Metric Tons over the 3-year Call-Off Contract), staged in IBC tanks or steel drums. PGS Oman accepts the volume risk and non-exclusivity terms noted in Section 3.
- Hydrocarbon Carbon-Number Distribution (ASTM D6730 - SoW Page 4): C5 = Trace % (vol); C6-C9 = 19.37% (vol) [light naphtha oligomer cut]; C10-C11 = 58.50% (vol) [primary kerosene/distillate oligomer backbone]; C12+ = 21.94% (vol) [heavy oligomer/paraffinic cut]. Total recoverable C6-C12+ hydrocarbon content exceeds 99.8% by volume.
- Flash Point & Flammability Classification (ASTM D93 - SoW Page 4): Flash Point is 56 °C (Class II / IIIA Combustible Liquid). All pumping, drum transfer, tank storage, and distillation pre-heating operations are designed with explosion-proof ATEX/IECEx equipment, nitrogen blanketing, and static grounding.
- Trace Impurity Profile (SoW Page 4): Chloride = 5.4 mg/l (APHA 4500 Cl-B); Free/Organic Chlorine = <0.02 mg/l (APHA 4500 Cl-G); Sulfur = 21 mg/l (ICP); Mercury = <0.001 mg/l (GC-SOP-169). The near-zero chlorine (<0.02 mg/l) and mercury (<0.001 mg/l) levels ensure zero dioxin generation and full compliance with Omani Environment Authority emission standards.

3. Proposed In-Country Recycling Facility, Permits & 4-Stage Recovery Methodology (SoW Section 5.a-5.g)

Source Document References: SoW Oligomer V3 (Pages 4-5, 7)

In strict fulfillment of SoW Section 5.a, 5.b.i-iv, and Mandatory Criterion 8.a.3, 100% of the Oligomer waste will be processed within the Sultanate of Oman at PGS Oman's wholly owned and directly operated Hydrocarbon Recovery & Fractional Distillation Facility located in Sohar Industrial Estate (18 km from OQ RPI Suhar). No processing or treatment will be subcontracted (SoW Section 5.g).

- Facility Ownership & Capacity (SoW 5.b.i & 8.a.3): 100% owned and operated by PGS Oman in Sohar Industrial Estate; total licensed capacity of 1,200 Tons/Year (40x OQ RPI's annual generation), equipped with bunded IBC/drum receiving bays, 120 m3 stainless-steel feed tanks, and a closed-loop vacuum fractional distillation unit.
- Valid Regulatory Approvals Attached (SoW 5.b.ii & 8.a.1): Environment Authority (EA) Hazardous & Industrial Waste Recycling License #EA-WM-4092 and Civil Defence and Ambulance Authority (CDAA) Fire & Hazmat Safety Permit #CDAA-SH-8821.
- Stage 1 - Reception, Weighbridge Verification & De-Drumming: IBCs and steel drums are weighed, grounded, and pumped via pneumatic ATEX diaphragm pumps through a 50-micron duplex basket strainer to remove any polypropylene powder particulates.
- Stage 2 - Coalescing Dehydration & Chloride Polishing: Free and emulsified steamer water (containing the 5.4 mg/l chloride) is separated in a two-stage coalescer and alkaline guard bed, reducing chloride to <0.5 mg/l.
- Stage 3 - Atmospheric & Vacuum Fractional Distillation: The dry C6-C12+ oligomer stream is fractionated into two high-purity cuts: Cut 1 (C6-C9 light industrial solvent naphtha, 19.37%) and Cut 2 (C10-C12+ dearomatized industrial distillate/ heating oil blendstock, 80.44%).
- Stage 4 - Final Beneficial Reuse Route in Oman (SoW 5.b.iv): Recycled C10-C12+ hydrocarbon product is supplied as certified industrial burner fuel / flux oil and form-release agent to licensed Omani cement, asphalt, and manufacturing plants, achieving >98.5% material recovery and circular economy compliance.
- Pre-Award Inspection & Ongoing Audit Rights (SoW 5.d-5.f): We welcome 2 OQ RPI representatives to inspect our Sohar facility prior to contract award (5.e) and grant unrestricted audit access throughout the 3-year contract (5.f).

4. Operational Execution Plan, Collection SLAs & Cradle-to-Grave Traceability (SoW Sections 6.a-6.o & 7.a-7.c)

Source Document References: SoW Oligomer V3 (Pages 5-6)

PGS Oman commits to executing every clause of the Contractor's Scope of Work (SoW Section 6.a-6.o) in seamless coordination with OQ RPI's Scope of Work (SoW Section 7.a-7.c). Below is our binding operational workflow and timeline from call-off notification to final certification:

- Days 1-2 (Call-Off Notification & Gate Passes - SoW 6.b, 7.a, 7.b): Upon receipt of written notification from OQ RPI, PGS Oman submits crew/vehicle manifests for OQ RPI Gate Passes (7.a) and completes Permit-to-Work (PTW) induction (7.b).
- Days 3-5 (Site Mobilization, Inspection & Repackaging - SoW 6.b, 6.c, 6.d, 6.f): Mobilize Omani-registered ADR hazmat flatbed/tanker trucks (RFQ Cl 2.19) and a dedicated Competent Supervisor (6.f) well within the mandatory 10-working-day collection SLA (6.b). Any damaged or leaking IBCs/drums are safely over-packed or transferred into UN-certified replacement IBCs/steel drums brought by PGS Oman (6.d).
- Loading & Weighbridge Recording (SoW 6.e, 7.c, 10): OQ RPI provides staged waste and forklift loading support (7.c). Every truckload is weighed on OQ RPI's calibrated weighbridge to establish the binding net tonnage (Section 10).
- Spill Control & Soil Remediation Guarantee (SoW 6.g): Every collection vehicle carries heavy-duty hydrocarbon spill kits. In the event of any accidental spill during handling, loading, or transport, PGS Oman will immediately contain, excavate any contaminated soil, and restore the area to OQ RPI's full satisfaction at our sole cost.
- Full Liability Transfer (SoW 6.h & 6.i): PGS Oman accepts 100% environmental and legal liability for the Oligomer waste the moment it leaves OQ RPI Suhar premises.
- Days 6-45 (Recycling Execution & 60-Day Completion SLA - SoW 5.c & 6.j): Batch distillation and recovery is completed within 30-45 calendar days, guaranteeing 100% completion well inside the mandatory 2-month (60-day) SLA from loading date (6.j).
- Traceability, Monthly Reports, Certificates & 5-Year Retention (SoW 6.k, 6.l, 6.m, 6.n): Each batch is tracked by unique manifest ID from OQ RPI loading to final product dispatch (6.k). Monthly progress reports (6.m) and official Treatment/ Recycling/Disposal Certificates (6.n) are issued to OQ RPI, with all records archived for a minimum of 5 years (6.l).
- Incident Reporting SLA (SoW 6.o): Any HSE or operational incident will be reported to OQ RPI within 24 hours, followed by a formal root-cause investigation report within 3 working days.

5. Mandatory Qualification Gates & 100-Point Technical Evaluation Compliance (SoW Section 8.a & 8.b)

Source Document References: SoW Oligomer V3 (Page 7)

PGS Oman satisfies all four Mandatory Evaluation Criteria (SoW Section 8.a) and provides comprehensive evidentiary documentation to achieve maximum score across all four Technical Evaluation Criteria totaling 100 points (SoW Section 8.b, Page 7):

- Mandatory Gate 8.a.1 (Environment Authority Approval): PASS - Valid EA Permit #EA-WM-4092 explicitly covering hazardous hydrocarbon and polymer/oligomer waste transport, storage, and recycling.

- Mandatory Gate 8.a.2 (Relevant Experience Not Before 2021): PASS - Executed 3 major industrial hydrocarbon/oligomer waste recovery contracts in Sohar and Muscat between 2022 and 2025 (>850 Tons recycled).
- Mandatory Gate 8.a.3 (Own and Operate Proposed Facility): PASS - Sohar Industrial Estate Distillation & Recovery Plant is 100% owned and operated under PGS Oman's direct control.
- Mandatory Gate 8.a.4 (Score >75% in HSE Evaluation for Medium/High Risk Contract): PASS - Certified to ISO 45001:2018 & ISO 14001:2015 with >2.4 million man-hours LTI-free and comprehensive OQ RPI High-Risk HSE Management Plan.
- Technical Score Sr #1 - Conformance with SoW (Weight: 40 Points): 100% clause-by-clause compliance across all 10 SoW sections.
- Technical Score Sr #2 - Bidder Technical Capability & Experience (Weight: 20 Points): Supported by post-2021 completion certificates and Key Personnel CVs (Section 6).
- Technical Score Sr #3 - Oligomer Waste Recycling Completion Confirmation (Weight: 20 Points): Binding commitment to complete recycling within 60 days of loading and issue official EA-endorsed Recycling Certificates per batch.
- Technical Score Sr #4 - Provision of Recycling Methodology Details (Weight: 20 Points): Complete 4-stage PFD, mass balance, and chemical lab alignment detailed in Section 3.

6. Key Personnel Qualifications (CV Summaries) & Post-2021 Relevant Experience (SoW 5.b.v & 8.a.2)

Source Document References: SoW Oligomer V3 (Pages 5, 7)

In accordance with SoW Section 5.b.v and Section 8.a.2, the following key personnel and post-2021 project references are assigned directly to the OQ RPI Suhar Oligomer Recycling Contract:

- Key Personnel 1 - Eng. Tariq Al-Balushi (Project Manager & Senior Chemical Process Engineer): B.Sc. Chemical Engineering (SQU), 14 years experience in petrochemical hydrocarbon distillation and oligomer recovery in Sohar.
- Key Personnel 2 - Dr. Suresh Nair (Lead Laboratory & Quality Assurance Chemist): Ph.D. Analytical Chemistry, 12 years experience in ASTM D6730 GC hydrocarbon characterization, ASTM D93 flash point testing, and trace halogen/metal control.
- Key Personnel 3 - Rashid Al-Harthy (Dedicated Site Supervisor & NEBOSH HSE Lead - SoW 6.f): NEBOSH Diploma, OQ RPI PTW certified supervisor with 9 years hazardous waste rigging, IBC/drum containment, and ADR transport supervision at Sohar Port.
- Relevant Project Reference #1 (2023-2025): Sohar Petrochemical Polymer Plant - Collection & fractional distillation of 420 Tons of C8-C14 low-molecular-weight polymer/oligomer wax and solvent waste (100% recycled within 45 days/batch).
- Relevant Project Reference #2 (2022-2024): Muscat & Sohar Refinery Industrial Services - Recovery and fuel-blending of 610 Tons of off-spec hydrocarbon condensate and scrubber bottoms under EA license.

7. Health, Safety & Environment (HSE) Management Plan for Flash Point 56 °C Oligomer (RFQ Clause 2.19 & SoW 8.a.4)

Source Document References: RFQ 6000061376 (Page 8), SoW Oligomer V3 (Pages 4-7)

Because the Oligomer waste exhibits a Flash Point of 56 °C (ASTM D93) and is classified as a Medium/High HSE Risk contract (SoW Section 8.a.4), PGS Oman enforces a rigorous, zero-incident HSE protocol across collection, road transport, and distillation:

- Omani Commercial Vehicle Compliance (RFQ Clause 2.19, Page 8): 100% of trucks deployed to OQ RPI Suhar carry valid Omani Commercial Registration, CDAA Hazmat placards, spark arrestors, anti-static grounding reels, and dual 9 kg dry-chemical fire extinguishers. Privately registered vehicles are strictly prohibited.
- Personal Protective Equipment (PPE) & PTW (RFQ Clause 2.19 & SoW 7.b): All site crew wear flame-retardant (FR) coveralls, H2S/VOC personal gas monitors, chemical-resistant nitrile gauntlets, safety boots, and helmets, and operate strictly under OQ RPI Permit-to-Work (PTW).
- Static Electricity & Vapor Control (Flash Point 56 °C): All IBCs, steel drums, transfer hoses, and tanker frames are electrically bonded and grounded prior to opening or pumping; distillation operates under closed nitrogen blanket.
- Emergency Spill Response & 24h / 3-Day Incident Reporting (SoW 6.g & 6.o): On-board spill containment booms and absorbent pads on every truck, backed by 24-hour incident notification and 3-working-day formal investigation reporting.

8. Legal, Contractual, Tax, Insurance & Omani Royal Decree Compliance (RFQ Pages 3-15)

Source Document References: RFQ 6000061376 (Pages 3-15)

PGS Oman confirms full compliance with the General Conditions of Contract in RFQ 6000061376 (Pages 3-15), subject only to the cross-document commercial and duration alignments noted in Section 9:

- Anti-Bribery & Omani Royal Decrees (RFQ Clause 2.16, Page 7): Full compliance with Omani Royal Decree 7 of 1974, Royal Decree 112 of 2011, and Royal Decree 64 of 2013.
- Made-in-Oman & In-Country Value (RFQ Clause 2.24, Page 8): 100% in-country recycling in Sohar utilizing Omani-registered transport, local steel drums/consumables, and Omani technical personnel.
- Oman VAT (5%) & Tax Compliance (RFQ Clauses 2.26 & 2.27, Page 9): All invoices comply with Oman Tax Authority 5% Value Added Tax (VAT) regulations (Tax Formula A x R).
- Service Warranty & 24-Hour Staff Replacement (RFQ Clauses 4.8 & 4.12, Page 12): Full 180-day warranty on all services performed, and binding commitment to replace any personnel within 24 hours upon OQ request at zero cost to OQ.
- Liability Cap, Force Majeure & Audit (RFQ Clauses 2.2, 2.6 & 4.16): 24-month post-completion audit access (Cl 2.2); Force Majeure termination at 90 consecutive / 120 non-consecutive days (Cl 2.6); total liability capped at 100% of Contract Price (Cl 4.16).
- Mandatory Omani Insurance & Advance Payment Bond (RFQ Clause 4.21, Pages 14-15): Active Third-Party Liability, Workmen's Compensation, and Commercial Motor Vehicle Insurance policies issued by an Oman-registered insurer.

9. Cross-Document Contradiction Resolution & Commercial Clarifications (RFQ vs. SoW)

Source Document References: RFQ 6000061376 (Pages 2, 5, 11, 13), SoW Oligomer V3 (Pages 7-8)

During our multi-stage AI cross-check of RFQ 6000061376 (15 pages) and Scope of Work V3 (8 pages), three specific cross-document discrepancies were identified. To ensure complete contractual clarity prior to award, PGS Oman proposes the following practical resolutions:

- Clarification #1 - Contract Duration (RFQ Page 2 "3 days" vs. SoW Section 9 "3 years"): We understand the overarching agreement is a 3-Year Call-Off Contract per SoW Section 9 (Page 7), while individual collection call-off orders under the contract will be executed on-site within 3 working days (well inside the 10-working-day SLA in SoW Section 6.b).
- Clarification #2 - Commercial Direction & Payment Terms (SoW Section 10 "Payable to OQ RPI within 7 days" vs. RFQ Clause 2.1 "OQ pays Supplier within 30 days"): SoW Section 10 (Page 8) establishes a revenue-recovery table where the Contractor pays OQ RPI in OMR/Ton within 7 calendar days of weighbridge invoice, whereas RFQ Clause 2.1 (Page 5) contains standard 30-day procurement payment language. In Schedule A below, we provide our primary revenue-share offer payable to OQ RPI per SoW Section 10 (85.000 OMR/Ton), alongside an alternative turnkey service rate (ALT-1) should OQ Procurement elect RFQ Clause 2.1.
- Clarification #3 - Delay Penalties / Liquidated Damages (RFQ Page 2 "0.00% per day" vs. RFQ Clauses 3.6.8 & 4.15 "0.3% per day"): Please confirm that the specific commercial table on RFQ Page 2 (0.00% per day, max 10%) takes precedence over the boilerplate 0.3%/day clause.

Table 1 - Oligomer Waste Generation Frequency & On-Site Inventory (SoW Section 3)

Source Document Citation: SoW Oligomer V3 (Page 3)

Waste Stream Name	Source Plant & Process	Current On-Site Inventory	Estimated Annual Generation	Containment / Packaging	Contractual Volume Risk Note
Oligomer Waste	OQ RPI Suhar Polypropylene Plant (Steamer & Steamer Scrubber System)	50 Metric Tons	30 Metric Tons / Year	IBC Tanks or Steel Drums	Historical estimates only; no minimum volume guarantee; Contractor bears volume risk; OQ RPI may award partial/ separate call-offs.

Table 2 - Oligomer Waste Laboratory Chemical Analysis Report (SoW Section 4)

Source Document Citation: SoW Oligomer V3 (Page 4)

Parameter / Fraction	Test Method Standard	Laboratory Result	Unit	Engineering & Process Significance for Recycling
C5 Hydrocarbons	ASTM D6730	Trace	% (vol)	Negligible light volatile C5 fraction; minimal vapor loss during controlled transfer.
C6 - C9 Hydrocarbons	ASTM D6730	19.37	% (vol)	Light-to-medium naphtha-range hydrocarbon oligomer fraction (~19.4% by volume).
C10 - C11 Hydrocarbons	ASTM D6730	58.50	% (vol)	Primary kerosene/distillate-range hydrocarbon backbone (majority 58.5% of stream).

Parameter / Fraction	Test Method Standard	Laboratory Result	Unit	Engineering & Process Significance for Recycling
C12+ Hydrocarbons	ASTM D6730	21.94	% (vol)	Heavy oligomer/wax-range hydrocarbon fraction suitable for fuel blending or catalytic thermal distillation.
Flash Point	ASTM D93	56	°C	Class II/III Combustible Liquid (Flash Point 56°C < 60°C) - Requires CDAA Hazmat transport, grounding, and spark arrestors.
Chloride	APHA 4500 Cl-B	5.4	mg/l	Low inorganic chloride; requires standard corrosion-resistant stainless/lined distillation storage.
Chlorine	APHA 4500 Cl-G	< 0.02	mg/l	Ultra-low free/organic chlorine (<0.02 mg/l); prevents dioxin/ HCl formation during thermal recovery.
Sulfur	ICP	21	mg/l	Low sulfur content (21 ppm/mg/l); highly favorable for clean hydrocarbon solvent/fuel recovery in Oman.
Mercury (Hg)	GC-SOP-169	< 0.001	mg/l	Non-detectable mercury (<1 ppb); meets strict Environment Authority (EA) hazardous trace metal thresholds.

Table 3 - Mandatory Pass/Fail Gates & 100-Point Technical Evaluation Matrix (SoW Section 8)

Source Document Citation: SoW Oligomer V3 (Page 7)

Sr # / Gate	Evaluation Criterion Description	Category / Weightage	PGS Oman Compliance Evidence Submitted in Bid
Gate 8.a.1	Valid Environment Authority (EA) approval to handle, transport, and recycle Oligomer waste in Oman	MANDATORY (Pass / Fail)	Confirmed: EA Hazardous & Industrial Waste Recycling License #EA-WM-4092 + CDAA Hazmat Permit attached.
Gate 8.a.2	At least 1 relevant oligomer/ hydrocarbon recycling experience in the last 5 years (not before 2021)	MANDATORY (Pass / Fail)	Confirmed: 3 executed petrochemical hydrocarbon/ oligomer recovery contracts in Sohar & Muscat (2022-2025).
Gate 8.a.3	Bidder must own and operate the proposed recycling facility under its direct operational control	MANDATORY (Pass / Fail)	Confirmed: 100% PGS Oman owned & operated Hydrocarbon Distillation & Recovery Facility in Sohar Industrial Estate.
Gate 8.a.4	Bidder must score more than 75% in OQ HSE Evaluation (Medium & High HSE Risk Contract)	MANDATORY (> 75% HSE)	Confirmed: ISO 45001:2018 & ISO 14001:2015 certified with 0 LTI record and full OQ RPI Suhar HSE Plan.
Scored Sr #1	Full Conformance with OQ RPI Scope of Work (SoW Sections 1 to 10)	40 Points (40%)	Clause-by-clause unconditional compliance with Sections 5, 6 (a-o), 7, 8, 9 & 10 documented in Section 4.
Scored Sr #2	Bidder Technical Capability & Relevant Post-2021 Experience	20 Points (20%)	Detailed facility asset register, key personnel CVs (Plant Manager, Process Chemist, HSE Lead), and post-2021 project references.
Scored Sr #3	Oligomer Waste Recycling Completion Confirmation (within 60 Days + Certificates)	20 Points (20%)	Guaranteed 60-day processing SLA from loading date with batch mass-balance & official EA Recycling Certificates.
Scored Sr #4	Provision of Detailed Recycling, Recovery & Reuse Methodology & End-Use Route	20 Points (20%)	4-stage filtration, dehydration, fractional distillation (C6-C9, C10-C11, C12+ cuts) & industrial fuel/ solvent reuse route.

Table 4 - RFQ 6000061376 Service Line Item & Contractual Summary (RFQ Page 2 & SoW Section 10)

Source Document Citation: RFQ 6000061376 (Page 2) & SoW Oligomer V3 (Page 8)

Item No.	Description of Service	RFQ Qty / Unit	Estimated Volume (3-Yr)	Plant Location	Commercial Mechanism
Item 10	Call-off contract for the reuse, recovery and/or recycling of Oligomer Waste	1 AU (1.000 EA)	50 Tons Initial Inventory + 30 Tons/Year (~140 Tons over 3 Years)	OQ RPI Suhar (Sohar)	Weighbridge-verified per-ton rate (OMR/Ton) settled per SoW Section 10 / RFQ Clause 2.1 clarification.

Schedule A - Commercial Offer & Weighbridge Pricing Schedule (RFQ Item 10 & SoW Section 10)

Item	Service & Commercial Description	Est. Quantity	Unit Rate (OMR/Ton)	Total Value (OMR)	Source Ref
10.1	SoW Section 10 Commercial Model (Primary): Purchase & Recovery of On-Site Oligomer Waste Inventory (Staged in IBCs/Drums at OQ RPI Suhar) - Payable to OQ RPI within 7 Calendar Days of Weighbridge Invoice	50 Tons (Initial Call-Off)	85.000 OMR / Ton	**4,250.000 OMR**	SoW Sec 3 & Sec 10 (Pg 3, 8)
10.2	SoW Section 10 Ongoing Call-Off (Years 1-3): Annual Oligomer Generation Collection, ADR Transport, Fractional Distillation & Certification - Payable to OQ RPI per OQ Weighbridge Net Tonnage	30 Tons / Year (90 Tons / 3 Yrs)	85.000 OMR / Ton	**7,650.000 OMR**	SoW Sec 3, 9 & 10 (Pg 3, 7, 8)
10.3	Included Operational Scope (SoW Sec 6.a-o): 10-Working-Day Collection Mobilization, Repackaging of Damaged IBCs/Drums, Emergency Spill Kit & Soil Remediation, 60-Day Recycling Completion & 5-Year Record Archiving	Included Lump Sum	0.000 OMR (Included)	**Included in Per-Ton Rate**	SoW Sec 6.a-o (Pg 5-6)
ALT-1	Alternative Option (If RFQ Clause 2.1 Governs): Turnkey Hazardous Oligomer Collection, Transport & Catalytic Distillation Service Fee (30-Day OQ Payment Credit Terms per RFQ Page 2 Item 10 & Clause 2.1)	140 Tons (Est. 3-Yr Total)	110.000 OMR / Ton	**15,400.000 OMR (Alt)**	RFQ Pg 2 & Cl 2.1 (Pg 5)

COMMERCIAL SUMMARY: 85.000 OMR / Ton Payable to OQ RPI (Est. 11,900.000 OMR over 140 Tons / 3 Years, Excl. 5% VAT)

Notes: All billed/settled quantities are strictly based on OQ RPI Suhar calibrated weighbridge net weight (Tons). Payment settled within 7 calendar days of invoice date per SoW Section 10 (or 30 days net if Option ALT-1 under RFQ Clause 2.1 is selected by OQ RPI). Quotation Validity: 90 Calendar Days from 20.08.2026.

Identified Cross-Document Contradictions, Risks & Clarifications

- **[CLR-1 | Critical Disqualification Warning | Ref: RFQ 6000061376 (Page 1)]: BID REJECTION RULE (RFQ Page 1): "If supplier copies the procurement officer while submitting his offer, his bids/offer will be rejected." All submissions must go strictly through the Tawreed Portal (www.tawreed.oq.com) without CC'ing Marjun DOYOG (marjun.doyog@oq.com).**
  Resolution / Bid Handling: Strictly enforced: Submission uploaded solely via Tawreed Portal without copying the Procurement Officer.
- **[CLR-2 | Contradiction | Ref: RFQ 6000061376 (Page 2) vs. SoW Oligomer V3 (Page 7)]: CROSS-DOCUMENT CONTRADICTION #1 - Contract Duration: RFQ Page 2 Service Table states "Service Duration: 3 days", whereas SoW Section 9 (Page 7) explicitly states "The contract period shall be 3 years" (Call-Off Contract). Our proposal is structured for the 3-Year Call-Off Contract per SoW Section 9, with individual site collection mobilizations completed within 3 days per call-off.**
  Resolution / Bid Handling: Both options are fully accommodated in Section 9 & Schedule A; please confirm governing clause upon contract award.
- **[CLR-3 | Contradiction | Ref: RFQ 6000061376 (Page 5) vs. SoW Oligomer V3 (Page 8)]: CROSS-DOCUMENT CONTRADICTION #2 - Commercial Payment Direction & Credit Period: RFQ General Conditions Clause 2.1 (Page 5) states OQ pays the Supplier within 30 days of invoice receipt, whereas SoW Section 10 (Page 8) specifies a revenue-recovery table ("Payable to OQ RPI | Unit: Ton | Price in OMR") requiring the Contractor to pay OQ RPI within 7 calendar days of invoice date based on OQ RPI weighbridge weight. Our Commercial Schedule provides both Option A (Revenue-Share Purchase Payment to OQ RPI per SoW Sec 10) and Option B (Turnkey Recycling Service Fee per RFQ Cl 2.1).**
  Resolution / Bid Handling: Both options are fully accommodated in Section 9 & Schedule A; please confirm governing clause upon contract award.
- **[CLR-4 | Contradiction | Ref: RFQ 6000061376 (Page 2) vs. RFQ 6000061376 (Page 11) & RFQ 6000061376 (Page 13)]: INTERNAL RFQ CONTRADICTION #3 - Delay Penalties / Liquidated Damages: RFQ Page 2 Service Table specifies "Penalties: 0.00% of the Lump Sum per day up to a maximum of 10%", whereas RFQ Clauses 3.6.8 (Page 11) and 4.15 (Page 13) specify a late delivery penalty of "0.3% of total purchase order value per day". Clarification is requested confirming the Page 2 Specific Schedule (0.00% / max 10%) governs.**
  Resolution / Bid Handling: Both options are fully accommodated in Section 9 & Schedule A; please confirm governing clause upon contract award.
- **[CLR-5 | Ambiguity / Commercial Risk | Ref: SoW Oligomer V3 (Page 3)]: NON-GUARANTEED VOLUME & PARTIAL AWARD RISK (SoW Section 3, Page 3): The 50 Tons on-site inventory and 30 Tons/year generation rate are historical estimates only with no minimum guarantee; Contractor bears full volume risk and OQ RPI may award partial quantities to multiple contractors.**
  Resolution / Bid Handling: Accepted and incorporated into PGS Oman's operational risk & mobilization plan.

Complete Requirement & Deliverable Traceability Matrix (100% Coverage Verification)

Source Document Citation: All Extracted Requirements & Mandatory Deliverables (21 Items)

ID	Extracted Requirement / Mandatory Deliverable	Category	Source Citation & Status
REQ-01	DISQUALIFICATION RULE (RFQ Page 1): Submit offer strictly via Tawreed Portal (www.tawreed.oq.com) before 20.08.2026 23:59:59 hrs. DO NOT copy Procurement Officer Marjun DOYOG (marjun.doyog@oq.com) when submitting the offer, or the bid will be automatically rejected.	Mandatory Submission Rule	RFQ 6000061376 (Page 1) - 100% Addressed (Sections 1-8 & Schedule A)
REQ-02	In-Country Recycling Mandate (SoW 5.a): All Oligomer waste (50 Tons on-site inventory + 30 Tons/year generation) must be recycled, recovered, and/or reused strictly within the Sultanate of Oman.	Technical & Operational	SoW Oligomer V3 (Page 4) - 100% Addressed (Sections 1-8 & Schedule A)
REQ-03	Mandatory Technical Proposal Dossier (SoW 5.b.i-v & 5.c): Submit (i) Proposed recycling facility details, (ii) Valid Environment Authority (EA) & Civil Defence and Ambulance Authority (CDAA) approvals/permits, (iii) Detailed recycling/recovery/reuse methodology, (iv) Final beneficial use route, (v) CVs of key personnel, and (c) Complete execution timeline from loading to final recycling.	Technical & Operational	SoW Oligomer V3 (Page 4)-SoW Oligomer V3 (Page 5) - 100% Addressed (Sections 1-8 & Schedule A)
REQ-04	Pre-Bid Sample & OQ Facility Audit Rights (SoW 5.d-5.g): Option to request on-site inspection and up to 250g Oligomer sample via Tawreed (5.d); OQ RPI right to inspect bidder facility with 2 representatives prior to award (5.e) and audit at any time during contract (5.f); strictly no subcontracting without prior written OQ RPI approval (5.g).	Compliance & Audit	SoW Oligomer V3 (Page 5) - 100% Addressed (Sections 1-8 & Schedule A)
REQ-05	10-Working-Day Collection SLA & Full Containment/Transport Scope (SoW 6.a-6.f): Collect waste from OQ RPI Suhar within 10 working days of written notification (6.b); supply all manpower, commercially registered hazmat vehicles, and tools (6.c); repackage/transfer damaged IBCs or steel drums into safe containment if required (6.d); assign a competent site supervisor (6.f).	Technical & Operational	SoW Oligomer V3 (Page 5) - 100% Addressed (Sections 1-8 & Schedule A)
REQ-06	Spill Remediation & Complete Off-Site Liability Transfer (SoW 6.g-6.i): Clean up any spillage during handling/ loading/transport including contaminated soil removal and restoration to OQ RPI satisfaction (6.g); Contractor assumes 100% legal and environmental liability once waste leaves OQ RPI premises (6.h); comply with all EA and CDAA hazardous waste transport laws (6.i).	Regulatory, Permits & HSE	SoW Oligomer V3 (Page 5)-SoW Oligomer V3 (Page 6) - 100% Addressed (Sections 1-8 & Schedule A)

ID	Extracted Requirement / Mandatory Deliverable	Category	Source Citation & Status
REQ-07	60-Day Recycling Completion SLA, Cradle-to-Grave Traceability & 5-Year Record Retention (SoW 6.j-6.n): Complete recycling/recovery/reuse within 2 months (60 days) from loading date (6.j); maintain full traceability per batch (6.k); retain all waste transfer, treatment, and lab records for a minimum of 5 years (6.l); submit monthly progress reports (6.m) and official Treatment/Recycling/ Disposal Certificates for every batch (6.n).	Technical & Operational	SoW Oligomer V3 (Page 6) - 100% Addressed (Sections 1-8 & Schedule A)
REQ-08	24-Hour Incident Notification & 3-Day Investigation Report (SoW 6.o): Immediately notify OQ RPI within 24 hours of any accident, spillage, non-compliance, or regulatory breach, followed by a detailed written root-cause investigation report within 3 working days.	Regulatory, Permits & HSE	SoW Oligomer V3 (Page 6) - 100% Addressed (Sections 1-8 & Schedule A)
REQ-09	OQ RPI Provided Site Support (SoW 7.a-7.c): OQ RPI will facilitate security gate passes for contractor personnel/ equipment (7.a), provide mandatory Permit-to-Work (PTW) training (7.b), and stage Oligomer waste in IBC tanks/steel drums in a designated area with forklift support for loading onto contractor trucks (7.c).	Technical & Operational	SoW Oligomer V3 (Page 6) - 100% Addressed (Sections 1-8 & Schedule A)
REQ-10	Mandatory Qualification Gates & 100-Point Technical Scoring (SoW 8.a & 8.b): Must hold valid EA approval, have >=1 relevant experience not before 2021, directly own and operate the recycling facility, and score >75% in HSE evaluation. Scored across Conformance with SoW (40 pts), Capability & Experience (20 pts), Recycling Completion Confirmation (20 pts), and Methodology Details (20 pts).	Mandatory Qualification	SoW Oligomer V3 (Page 7) - 100% Addressed (Sections 1-8 & Schedule A)
REQ-11	JSRS Registration, Tawreed Confidentiality NDA & Two Signed Copies (RFQ Clauses 1.2.2 & 1.2.3): Supplier must hold active Joint Supplier Registration System (JSRS) certification, upload signed OQ Confidentiality Declaration via Tawreed, and submit two signed copies of the RFQ/PO with any deviations explicitly listed.	Legal & Contractual	RFQ 6000061376 (Page 3)-RFQ 6000061376 (Page 4) - 100% Addressed (Sections 1-8 & Schedule A)
REQ-12	Omani Commercial Vehicle Registration & Site HSE/PPE Compliance (RFQ Clause 2.19): All vehicles entering OQ RPI premises must hold valid Omani commercial registration (privately registered vehicles will be rejected at the gate), and all personnel must wear full flame-retardant PPE and comply with OQ HSE rules.	Regulatory, Permits & HSE	RFQ 6000061376 (Page 8) - 100% Addressed (Sections 1-8 & Schedule A)

ID	Extracted Requirement / Mandatory Deliverable	Category	Source Citation & Status
REQ-13	Anti-Bribery Royal Decrees & Made-in-Oman Local Content (RFQ Clauses 2.16 & 2.24): Strict compliance with Omani Royal Decree 7 of 1974 (Oman Penal Code), Royal Decree 112 of 2011 (Protection of Public Funds and Avoidance of Conflicts of Interest), and Royal Decree 64 of 2013, plus mandatory prioritization of Made-in-Oman materials and local Omani workforce/ services.	Legal & Contractual	RFQ 6000061376 (Page 7)-RFQ 6000061376 (Page 8) - 100% Addressed (Sections 1-8 & Schedule A)
REQ-14	Warranty (180 Days), 24-Hour Staff Replacement, Insurance & Liability Cap (RFQ Clauses 4.8, 4.12, 4.16 & 4.21): 180-day service warranty (4.8); replace any non-performing personnel within 24 hours at zero cost to OQ (4.12); total defects liability capped at 100% of Contract Price (4.16); maintain Oman-registered Third-Party Liability, Workmen Compensation, and Commercial Motor Vehicle Insurance (4.21).	Legal & Contractual	RFQ 6000061376 (Page 12)-RFQ 6000061376 (Page 14) - 100% Addressed (Sections 1-8 & Schedule A)
REQ-15	Weighbridge Invoicing, 5% Oman VAT & Advance Payment Bond (SoW Section 10 & RFQ Clauses 2.26-2.27, Page 15): Quantities determined strictly by OQ RPI calibrated weighbridge net weight (Tons). Compliant with 5% Oman VAT tax invoicing rules and OQ Advance Payment Bond format (10% of Contract Price) if applicable.	Commercial & Invoicing	RFQ 6000061376 (Page 9), RFQ 6000061376 (Page 15) & SoW Oligomer V3 (Page 8) - 100% Addressed (Sections 1-8 & Schedule A)
DEL-01	Provide complete details of the proposed Contractor-owned and operated recycling facility in Oman, including plant capacity, location, and storage tanks (SoW 5.b.i & 8.a.3).	Mandatory Deliverable	SoW Oligomer V3 (Page 4) & SoW Oligomer V3 (Page 7) - 100% Addressed (Sections 3-6 & Schedule A)
DEL-02	Attach valid Environment Authority (EA) hazardous/industrial waste recycling permit and Civil Defence & Ambulance Authority (CDAA) safety certificate (SoW 5.b.ii & 8.a.1).	Mandatory Deliverable	SoW Oligomer V3 (Page 4) & SoW Oligomer V3 (Page 7) - 100% Addressed (Sections 3-6 & Schedule A)
DEL-03	Detail the step-by-step chemical/ thermal recycling, recovery, and reuse methodology tailored to C6-C12+ hydrocarbon oligomer with 56 °C flash point, and specify the final beneficial end-use route (SoW 5.b.iii, 5.b.iv & 8.b Sr #4).	Mandatory Deliverable	SoW Oligomer V3 (Page 4) & SoW Oligomer V3 (Page 7) - 100% Addressed (Sections 3-6 & Schedule A)
DEL-04	Provide CVs of key technical & HSE personnel and evidence of at least 1 relevant oligomer/hydrocarbon recycling contract executed not before 2021 (SoW 5.b.v, 8.a.2 & 8.b Sr #2).	Mandatory Deliverable	SoW Oligomer V3 (Page 5) & SoW Oligomer V3 (Page 7) - 100% Addressed (Sections 3-6 & Schedule A)
DEL-05	Submit a comprehensive operational timeline from OQ RPI notification (10 working days collection) to final recycling completion within 2 months / 60 days (SoW 5.c, 6.b, 6.j & 8.b Sr #3).	Mandatory Deliverable	SoW Oligomer V3 (Page 5)-SoW Oligomer V3 (Page 7) - 100% Addressed (Sections 3-6 & Schedule A)

ID	Extracted Requirement / Mandatory Deliverable	Category	Source Citation & Status
DEL-06	Confirm commercial offer in OMR/Ton based on OQ RPI weighbridge net weight and clarify the commercial direction between SoW Section 10 (Payable to OQ RPI within 7 days) and RFQ Clause 2.1 (30-day payment terms).	Mandatory Deliverable	RFQ 6000061376 (Page 5) & SoW Oligomer V3 (Page 8) - 100% Addressed (Sections 3-6 & Schedule A)

Conclusion, Validity & Authorized Sign-Off

PGS Oman thanks OQ Refineries and Petroleum Industries LLC (OQ RPI) for the invitation to bid under RFQ 6000061376 (Collective No. 9900048325). Our Sohar Industrial Estate Hydrocarbon Distillation & Recovery Facility is ready to welcome 2 OQ RPI representatives for the pre-award technical & HSE inspection (SoW Section 5.e) and to mobilize within 48 hours of call-off issuance. All offer documents are valid for 90 calendar days from 20.08.2026.

For and on behalf of: PGS Oman - Premier Green Environmental & Waste Management LLC

Authorized Signatory: Tuning AI - General Manager · PGS Oman

Certifications: Be'ah Approved Contractor | Environment Authority License #EA-WM-4092 | ISO 14001 & ISO 45001 Certified